

数量総括表

諏訪郡 下諏訪町 樋橋～町屋敷2工区

工種	名称・規格	計算式等	単位	数量	適要
舗装修繕工事費					
道路修繕					
車道舗装修繕工					
路面切削・破碎工					
	路面切削工		m ²	3,002	平均 t=5cm
	廃材運搬工	3002.5*0.05	m ³	150	切削廃材
	舗装切断工	310.0+9.8+9.8	m	329	
	舗装版掘削積込		m ²	3,002	平均 t=10cm
	廃材運搬工	3002.5*0.1	m ³	300	掘削廃材
	機械掘削	3002.5*0.15	"	450	平均 t=15cm
	残土処分		"	450	土砂
	切削廃材処分費	150.1*2.3	t	345	
	掘削廃材処分費	300.3*2.3	"	690	
舗装工					
	不陸整正		m ²	3,002	
	As安定処理工		"	3,002	t=10cm
	基層・中間層工		"	3,002	t=15cm
	表層工		"	3,002	t=5cm
安全施設工					
区画線設置工					
	区画線設置工		m	310	ペイント黄実W=30cm
	区画線設置工	310×2	"	620	ペイント白実W=15cm
	色換え作業		回	1	
運搬費					
	運搬費		式	1	
安全費					
	交通誘導員		人	135	

面積計算書											
測点	幅員(法長)		平均幅員(平均法長)			距離	面積(m ²)			備考	
	舗装切削	舗装取壊	舗装切削	舗装取壊	舗装切削		舗装取壊	舗装取壊			
BP	0.00	9.8	9.8		-	-	-	-	-	-	
	50.00	9.8	9.8		9.80	9.80		50.0	490.0	490.0	
	100.00	9.8	9.8		9.80	9.80		50.0	490.0	490.0	
	120.00	9.2	9.2		9.50	9.50		20.0	190.0	190.0	
	170.00	9.2	9.2		9.20	9.20		50.0	460.0	460.0	
	200.00	9.9	9.9		9.55	9.55		30.0	286.5	286.5	
	250.00	9.9	9.9		9.90	9.90		50.0	495.0	495.0	
EP	310.00	9.8	9.8		9.85	9.85		60.0	591.0	591.0	
合計								310.0	3,002.5	3,002.5	0.0